BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT41616/CALL-2

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/05/2020-21, Date: 27.07.2020

Name of Work:Improvements to drains cross roads of B Krishnappa layout in amruthahalli in ward no.07 Byataranapura.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of ANJAN KUMAR Y A ( )	
				In Figures	In Words
1	68.25	Removing and refixing stone slabs of drains and pointing in CM(1:3)	Sqm	111.0	Rupees One Hundred Eleven
2	290.7	Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications	cum	137.8	Rupees One Hundred Thirty Seven and Eighty Paise Only
3	71.62	Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM curing complete as per specifications.	cum	5505.0	Rupees Five Thousand Five Hundred Five Only
4	91.28	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.878 cum and fine aggragtes @ 0.53cum, machine mixed concrete laid in layers not eceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing complate as per specifications	cum	5747.32	Rupees Five Thousand Seven Hundred Forty Seven and Thirty Two Paise Only
5	3.54	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications	tonne	72326.0	Rupees Seventy Two Thousand Three Hundred Twenty Six Only
6	528	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular slabs /side walls polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge.	Sqm	483.36	Rupees Four Hundred Eighty Three and Thirty Six Paise Only
7	194.25	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete10cms thick.	Sqm	966.72	Rupees Nine Hundred Sixty Six
8	165	Providing one line dressing to granite stone slabs/granite stone masonry as per specifications.	Sqm	950.82	Rupees Nine Hundred Fifty and Eighty Two Paise
9	785	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 of size 450x150x500 mm and finished with CM 1:3 plastering and finishing cutting etc., complete	nos	467.46	Rupees Four Hundred Sixty Seven and Forty Six Paise Only
10	353.25	Providing and applying ready mix priming coat over ocncrete / masonry, / asbestos cement sheet / plastered surfaces includding preparing the surface after thorougly cleaning of oil, grease, dirt and other foreign matter and sand papering including cost of materials, labour compelte as per specifications.	Sqm	39.22	Rupees Thirty Nine and Twenty Two Paise Only
11	290.7	Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification	cum	94.34	Rupees Ninety Four and Thirty Four Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92